

GENERAL EXTERIOR NOTES:

- REFER TO BUILDING SYSTEMS FOR ADDITIONAL EXTERIOR WALL AND MATERIAL INFORMATION
- REFER TO SPECIFICATION FOR DETAILED EXTERIOR MATERIAL INFORMATION

KEYNOTES:

- A50 METAL PARAPET CAP
E1 BRAVISSI STONE BASE WITH CAST STONE CAP
E2 CEMENT STUCCO, TAN
E3 FIBER CEMENT LAP SIDING, 6" REVEAL, BRICK RED
E4 MASONRY BRICK VENEER
E7 SUN SHADE; DARK BRONZE
E8 ANODIZED ALUMINUM STOREFRONT ENTRY SYSTEM; DARK BRONZE
E9 MAGIC PAK LOUVER; FINISH TO MATCH ADJACENT
E10 FIBERGLASS WINDOW; WHITE
E14 FIBERGLASS ENTRY DOOR; INSULATED
E15 INSULATED HOLLOW METAL DOOR; PAINT TO MATCH ADJACENT MATERIAL
E19 FIBER CEMENT WOOD LOOK SHAKE SIDING



PPL Union Congregational Housing

3700 Alabama Avenue S, St. Louis Park, MN

URBANWORKS

CONSULTANT

PRELIMINARY
NOT FOR
CONSTRUCTION

PUD RESUBMITTAL
05.27.2020

REVISIONS

DATE 05/08/2020
PROJECT # 19-0037
PHASE SD
DRAWN BY MEB
CHECKED BY MEB

BUILDING
ELEVATIONS

A303



3 East - Inside Elevation - Color

OVERALL ELEVATION 2257 SF
FIBER CEMENT WOOD LOOK SIDING 194/2257 = 8.6%
FIBER CEMENT LAP SIDING 413/2257 = 18.3%
STONE MASONRY 0/2257 = 0%
GLAZING/WINDOWS 593/2257 = 26.3%
BRICK 283/2257 = 12.5%
STUCCO 774/2257 = 34.3%



2 East Elevation - Color

OVERALL ELEVATION 4768 SF
FIBER CEMENT WOOD LOOK SIDING 587/4768 = 12.3%
FIBER CEMENT LAP SIDING 467/4768 = 9.8%
STONE MASONRY 699/4768 = 14.7%
GLAZING/WINDOWS 1122/4768 = 23.5%
BRICK 801/4768 = 16.8%
STUCCO 1092/4768 = 22.9%



1 North Elevation - Color

OVERALL ELEVATION 10598 SF
FIBER CEMENT WOOD LOOK SIDING 1026/10598 = 9.7%
FIBER CEMENT LAP SIDING 1322/10598 = 12.5%
STONE MASONRY 405/10598 = 3.8%
GLAZING/WINDOWS 2546/10598 = 24.1%
BRICK 1905/10598 = 17.9%
STUCCO 3394/10598 = 32.0%

C:\I\ext\Project Files\19-0037 A20 Flat Roof 3 Story Central_mary.janet.txd
5/27/2020 12:58:45 PM



1 South Elevation - Color
A304 3/32" = 1'-0"

OVERALL ELEVATION 10636 SF
FIBER CEMENT WOOD LOOK SIDING 1145/10636 = 10.8%
FIBER CEMENT LAP SIDING 1396/10636 = 13.1%
STONE MASONRY 431/10636 = 4.1%
GLAZING/WINDOWS 2803/10636 = 26.4%
BRICK 1744/10636 = 16.4%
STUCCO 3117/10636 = 29.2%



3 West - Inside Elevation - Color
A304 3/32" = 1'-0"

OVERALL ELEVATION 1732 SF
FIBER CEMENT WOOD LOOK SIDING 194/1732 = 11.2%
FIBER CEMENT LAP SIDING 234/1732 = 13.5%
STONE MASONRY 46/1732 = 2.6%
GLAZING/WINDOWS 446/1732 = 25.8%
BRICK 277/1732 = 13.1%
STUCCO 585/1732 = 33.8%



2 West Elevation - Color
A304 3/32" = 1'-0"

OVERALL ELEVATION 4520 SF
FIBER CEMENT WOOD LOOK SIDING 699/4520 = 15.5%
FIBER CEMENT LAP SIDING 442/4520 = 9.8%
STONE MASONRY 0/4520 = 0%
GLAZING/WINDOWS 1354/4520 = 30.0%
BRICK 925/4520 = 20.5%
STUCCO 1100/4520 = 24.2%

GENERAL EXTERIOR NOTES:

- REFER TO BUILDING SYSTEMS FOR ADDITIONAL EXTERIOR WALL AND MATERIAL INFORMATION
- REFER TO SPECIFICATION FOR DETAILED EXTERIOR MATERIAL INFORMATION

KEYNOTES:

- E1 BRAVISSI STONE BASE WITH CAST STONE CAP
- E2 CEMENT STUCCO, TAN
- E3 FIBER CEMENT LAP SIDING, 6" REVEAL, BRICK RED
- E4 MASONRY BRICK VENEER
- E7 SUN SHADE; DARK BRONZE
- E10 FIBERGLASS WINDOW; WHITE
- E13 OVERHEAD GARAGE DOOR
- E14 FIBERGLASS ENTRY DOOR; INSULATED
- E15 INSULATED HOLLOW METAL DOOR; PAINT TO MATCH ADJACENT MATERIAL
- E19 FIBER CEMENT WOOD LOOK SHAKE SIDING

URBANWORKS

CONSULTANT

PRELIMINARY

**NOT FOR
CONSTRUCTION**

PUD RESUBMITTAL
05.27.2020

REVISIONS

DATE 05/08/2020
PROJECT # 19-0037
PHASE SD
DRAWN BY MEB
CHECKED BY MEB

**BUILDING
ELEVATIONS**

A304



PPL Union Congregational Housing

3700 Alabama Avenue S, St. Louis Park, MN

© URBANWORKS ARCHITECTURE LLC 2020
901 NORTH THIRD STREET, SUITE 145, MINNEAPOLIS, MN 55401