




NOTES:

1. INSTALL ADA APPROVED PEDESTRIAN CURB RAMPS AT ALL INTERSECTIONS. SEE MNDOT STANDARD PLAN 5-297.250 FOR DETAILS.
2. THE PROFILE GRADE OF THE TRAIL SHALL NOT EXCEED THE GRADE OF THE ADJACENT ROADWAY UNLESS AUTHORIZED BY THE CITY ENGINEER.
3. THE WIDTH OF THE TRUNCATED DOMES AT THE CURB RAMP MUST BE GREATER THAN OR EQUAL TO THE WIDTH OF THE TRAIL.
4. A 2' (MINIMUM) CLEAR ZONE IS REQUIRED ON BOTH SIDES OF TRAIL.